

RESIDENT WELFARE ASSOCIATION

Regn No 613/2009-10
 Telephone: 0120-4272990
 E-mail:- awhotownshipgn@gmail.com
 Website- www.awhogvgn.com

AWHO Township
 Gurjider Vihar
 Pocket P-5, Sector Chi I,
 Greater Noida
 GB Nagar (UP)
 Pin - 201310

10103/RWA/GVGN/QUOTATION

Dec. 2023

.....

**CALL FOR QUOTATION FOR TOWER TERRACE FIBRE REINFORCED ELASTOMERIC LIQUID WATERPROOFING
 WORK WITH MATERIAL AND LABOUR**

1. Quotation is invited for the following work in Gurjinder Vihar, AWHO Township, Greater Noida:-

Sr.no	Work Description	Unit	Qty. (Approx.)	Rate	Amount (in Rs.)
	The Fibre reinforced Elastomeric liquid Water Proofing Work will be completed as under mentioned items.(For 10 no roof)				
(A)	Surface preparation for Fibre reinforced Elastomeric liquid Water Proofing Work.				
a)	Removing all loose material like cement flakes, loose mortar plaster, alge formation and other unwanted particles, wherever required including flat roof with vertical cobing side plaster.	Sqm.	1000		
b)	Cleaning the surface with air blower/ by pressure to make it clean and dust free. Drying the surface damp, free from standing water.				
c)	Providing and laying of a 75 x 75 mm coving with polymer modified mortar at floor wall joints wherever required.				
d)	Providing and laying 01 coat of polymer diluted with water in ratio of 1:3 with cement over entire clean and prepared surface as bond coat cementious coating.				
e)	Providing and laying average 25 mm thick cement sand plaster in CM 1:4 (1 Cement:4 Coarse sand) with integral waterproofing compound @ 200 ml per bag of cement including flat roof with vertical cobing side with curing upto 07 days. The mortar should be laid merging with the existing slope of the roof.				

(B)	Fibre reinforced Elastomeric liquid Water Proofing Work				
a)	Suppling and applying 01 coat of Prime seal primer dilute with water in the ratio 2:1 spreading at the rate of 8.0 Sqm/litre in the SSD condition.	Sqm.	1000		
b)	Suppling and applying fibre reinforced elastomeric liquid water proofing membrane without dilution spreading at the rate of 0.70 litre/Sqm/Coat to achieve total dry film thickness of 850 to 1000 microns at forced coverage at the rate of 1.40 litre/ Sqm in 2 coats as per manufacturers specification.				
	NOTE:				
	i) Water testing (Ponding) shall be carried out for minimum 96 hours.				
	ii) Warranty: 12 yrs from the date of complition of each roof.				
	iii) Payment will be released on actualcompleted and Tested for each roof.				
	iv) 10 % amount of gross work completed will be deducted as a retention/warranty from RA Bills and refunded after two years of complition of work.				
	v) Debris material should be stacked near at ground as directed and or to be disposed off outside the premises of AWHO by vendor.				
	vi) Depending upon the quality of work, AWHO RWA representative/Engineer in charge have full power to cancelled /extend your work order beyond 10 roofs on the same Terms/Conditions and cost.				

- 2) The Quotation is to be returned duly quoting your rate to the President RWA AWHO Township, Gurjinder Vihar, Greater Noida(UP).
Sealed/by e.mail (**E.mail - tenders.awhogn@gmail.com**) quotation may be dropped in sealed envelope in the Tender box kept in Room no 2 at RWA office by 1700 Hrs on **26/12/2023** , If quotation is not received by due date and time, then you will be considered as unwilling to do the work. The quotations shall be opened at 1100 Hrs. on **27/12/2023**.

Note:-

- i) For details, work site can be seen on any working day before giving of Quotation.
- ii) Water shall be provided free of cost & Electricity will be chargeble on nominal rate.
- iii) GST if applicalble, to be indicated seperately.
- iv) No accomodations will be provided. Accomodation if required for storage purpose only can be provided for nominal rent charges.

Jeetendra Kumar Thakur
Civil Engineer

(Col. N K Sharma)
Member Maint.